

Guyana Shore Base Inc.

Technical Specification

Supply and Installation of Flatpacks for G-Store 1 McDoom, East Bank Demerara.

Quantity	Description
5	<p>Supply and Installation of 5x Flatpacks as per attached layout.</p> <p>Notes:</p> <p>The office area shall consist of 5 each flatpacks installed on the foundation blocks, with the layout – 1 single office, 1 toilet/washroom area (2 x unisex toilets) and 1 open plan office area, 1- Break /lunchroom.</p> <p>The office building shall be constructed with a secondary roof, 1 -stair/landing as per layout, 4 ea. x AC units (1ea. in break room. 2 ea. in open office area, 1 ea. in single office).</p> <p>The office furniture per layout (8 desks, and 8 chairs each).</p> <p>Break room: Counter with the installed sink, 2 tables, 8 chairs (as per layout).</p> <p>Washroom: 2 x unisex toilets with fully enclosed toilet cabins, each cabin with sink, toilet bowl, toilets shall have intake and exhaust ventilation.</p>