

## Scope of Work

The contractor shall execute all electrical work as per the drawings provided and client requirements. This includes the installation of an electrical connection of electrical equipment, cables, distribution panels, conduits, and components as detailed in the design drawings. The contractor shall conduct testing of all installed systems to ensure functionality and compliance with the required local standards and provide test reports. Upon completion, the contractor must submit as-built drawings and documentation reflecting any changes made during execution.

#### **Contractor Requirements**

- Ensure adequate manpower equipped with proper skills to complete the scope of work.
- Supply PPE for all personnel and enforce its usage throughout the project.
- Provide all necessary tools required to complete the scope of work.

### **Electrical Installation**

- Install electrical equipment, cables, conduits, and components as specified in the design drawings.
- Group Marking for Equipment: Clearly mark the groups assigned to each installed electrical equipment (receptacles, junction boxes, etc.) as per design.
- Breaker Group Marking: Clearly label the groups on breakers within the distribution panels in accordance with the design

### Testing

Contractor shall conduct the following tests to ensure functionality, safety, and compliance with Guyana's local standards:

- **Cable Insulation Testing:** Test all installed cables to ensure they meet the required insulation resistance levels.
- **Conductivity Testing:** Verify proper current flow and the integrity of all electrical connections, terminations, and conductors.
- **Grounding System Testing:** Measure ground resistance levels to confirm compliance with the required standards

### Deliverables

The following deliverables must be provided:

- Simplified schedule outlining the timeline for execution.
- Detailed as-built drawings and documentation reflecting all changes made during the project in PDF and CAD formats.
- Test reports, including insulation resistance, conductivity, and grounding results.
- Calibration certificates for testing equipment
- Cable log documenting the type, length, and installation details of all cables used in the project.

### **Approval and Acceptance**

The contractor must get client approval for any changes to the design or scope before implementation. Final approval will be given after completion of installation work, testing, and submitting deliverables

# www.gysbi.com



PANEL SCHEDULES







						LOAD SUMMARY					
					480/2	77V, 3 PHASE, 60HZ	SUPPLY				
(	Circuits	Equipment Name	Circuit Breaker	Voltage/ Phase	Connected Load (W)	Cable size (mm2)	Cable Length (ft)	Voltage Drop (Actual) %	Voltage Drop (Permissible) %	Cable type	Comments
AA-	1,3,5	Lathe (15HP, 21FLA)	40A/3P	480/3P	17,460	4x16 (3L, 1G)	96	2.99	3	metal clad	
AA-	2,4,6	Drill Press	30A/3P	480/3P	6600	4x10 (3L, 1G)	80	2.96	3	metal clad	
AA-	7,9,11	GOFF Blaster (15HP, 21FLA)	40A/3P	480/3P	17,460	4x16 (3L, 1G)	122	2.85	3	metal clad	
AA-	8,10,12	2 Ton Crane	40A/3P	480/3P	3020	4x6 (3L, 1G)	25	2.07	3	metal clad	
AA-	13,15,17	2 Ton Crane	40A/3P	480/3P	3020	4x16 (3L, 1G)	100	2.33	3	metal clad	
AA-	14,16,18	10 ton Gorbel Crane	30A/3P	480/3P	14965	4x16 (3L, 1G)	90	2.80	3	metal clad	
AA-	19,21,23	Roof mounted blast fan	15A/3P	460/230/3P	2000	4x4 (3L, 1G)	150	2.33	3	metal clad	
AA-	20,22,24	Roof mounted blast fan	15A/3P	460/230/3P	2000	4x4 (3L, 1G)	90	1.40	3	metal clad	
AA-	25,27,29	Roof mounted blast fan	15A/3P	480/230/3P	2000	4x4 (3L, 1G)	150	2.33	3	metal clad	
AA-	22,28,30	Door Motor	15A/3P	15A/3P	1000	4x4 (3L, 1G)	160	2.49	3	metal clad	
AA-	31	Highbay lights & Drivers(8)	15A/1P	277/1P	1400	4 x 4 (2L, 1N, 1G)	230	2.64	3	metal clad	
		Highbay lights & Drivers(8)	15A/1P	277/1P	1400	4 x 4 (2L, 1N, 1G)	160	2.49	3	metal clad	
		Highbay lights Panel to switch	15A/1P	277/1P	2640	3 x 4 (1L, 1N, 1G)	115	2.86	3	metal clad	
		36 cct 3 Phase Panel cable	125/3P	480		4 X 50(3L, 1N)	15			xlpe armoured	
		Total			74,965						
					230/1	10V, 3 PHASE, 60HZ	SUPPLY				
BB-	1,3	Mill	20/2P	230/120/2P	3840	4x6 (2L, 1N, 1G)	60	2.87	3	metal clad	
BB-	2	Work Station	20A/1P	120/1P	1500	3x6 (1L, 1N, 1G)	60	2.87	3	metal clad	
BB-	4	Work Station	20A/1P	120/1P	1500	3x16 (1L, 1N, 1G)	125	2.24	3	metal clad	
BB-	5	Test stand	20A/1P	120/1P	1500	3x10 (1L, 1N, 1G)	100	2.85	3	metal clad	
BB-	6	1/2 ton JIB Crane (2)	30A/1P	120/1P	2160	3x16 (1L, 1N, 1G)	165	2.96	3	metal clad	
BB-	7	Power to GOFF Blaster control	15A	120/1P	1000	3x4 (1L, 1N, 1G)	125	2.25	3	metal clad	
BB-	8	Power to 2 ton crane control	15A	120/1P	1000	3x4 (1L, 1N, 1G)	110	1.98	3	metal clad	
BB-	9	Power to 2 ton crane control	15A	120/1P	1000	3x4 (1L, 1N, 1G)	25	0.45	3	metal clad	
BB-	10	Power to 10 ton crane control	15A	120/1P	1000	3x4 (1L, 1N, 1G)	100	1.80	3	metal clad	
BB-	11	Power to JIBB crane control	15A	120/1P	1000	3x6 (1L, 1N, 1G)	200	2.39	3	metal clad	
		Total			15,500						

	230/110V, 3P, 60Hz Supply		480/277V, 3P, 60Hz Supply
oad 15,500	Total load	74,965	Total load
, 3P 40	Total current at 230V, 3P	92	Total current at 480V, 3P
led 60A	Recommended	125A	Recommended