SUPPLY AND INSTALLATION OF SHELVES, NEW FILING ROOM, FIRST FLOOR, MAIN OFFICE BILL NO.1 - FURNITURE

Ref	Description	Unit	Qty	Rate	Amount
	A35 EMPLOYER'S REQUIREMENTS: SPECIFIC LIMITATIONS ON METHOD/ SEQUENCE/ TIMING/ USE OF SITE				
2.1	Site Access: All personnel require the company's approval for acces to the site. Contractor's Personnel requiring access shall request access via https://visit.gysbi.gy/register.	-	-	-	-
2.2	Induction Training: Before the execution of any works on the company's property, the Contractor's employees shall attend an induction training for intended to inform the Contractor's employees of GYSBI's QHSSE policies. The training exercise will be conducted over a period one (1) day.	-	-	-	-
2.3	Start of Work: No work activity shall commence without a Permit to Work (PTW) issued by the Base Manager/ Area Authority as applicable. PTW applications are to be submitted a minimum of 24 hours prior to the commencement of the shift.	-	-	-	-
	N FURNITURE/ EQUIPMENT				
	N10 GENERAL FIXTURES/ FURNISHINGS/ EQUIPMENT				
	Supply and install shelves; in accordance with the Drawings; pine wood; sanded and painted with 2 coats of matte black paint. Rate to include for all components and fixtures including stabilizing brackets and stabilizing boards.				
2.4	- Type 1; 60" long x 12" deep x 98.5" high	Nr.	6		
2.5	- Type 2; 42" long x 12" deep x 98.5" high	Nr.	3		
2.6	- Type 3; 30" long x 12" deep x 98.5" high	Nr.	3		
2.7	- Type 5; 60" long x 12" deep x 82.75" high	Nr.	2		
	Relocate and modify shelves; two (2) tiers; pine wood; wall mounted with 9" x 9" x 1/8" thick brackets spaced at 24"; with toe and side boards; sanded and painted with 2 coats of matte black paint, all in accordance with the Drawings. Rate to include for fasteners, touch-up paining, etc. Mounting height to be determined on site.				
2.8	- Type 4; 132" long x 12" deep x 12" high	Nr.	1		
2.9	- Type 4; 36" long x 12" deep x 12" high	Nr.	1		
	Total (Guy\$)				

01-Storage (2) Page 1 of 1